


# versatile™ 4C Mailbox, 4C15D-17



COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.
MAILBOX	MB1	3\" H x 12\" W x 15\" D	17
OUTGOING MAIL	OM2	6-1/2\" H x 12\" W x 15\" D	1
PARCEL	PL5	17\" H x 12\" W x 15\" D	1
PARCEL	PL6	20-1/2\" H x 12\" W x 15\" D	1

**Notes:**

1. This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
  - a. At least one customer compartment shall be positioned less than 48\" AFF.
  - b. No parcel locker (interior bottom shelf) shall be positioned less than 15\" AFF.
  - c. No patron (tenant) lock shall be positioned more than 67\" AFF.
  - d. No customer compartment (interior bottom shelf) shall be positioned less than 28\" AFF.
  - e. The USPS Arrow lock shall be positioned 36\"- 48\" AFF.
2. This 4C mailbox can also be used for private applications.
3. The rough opening width for multi-unit 4C installations is provided using the Florence configurator: [www.florencemailboxes.com/configurator](http://www.florencemailboxes.com/configurator).

PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX

**FLORENCE**  
**CORPORATION**

5935 Corporate Drive • Manhattan, KS 66503  
 800.275.1747 • [www.florencemailboxes.com](http://www.florencemailboxes.com)

MODEL 4C15D-17	REV D
SCALE NONE	LAST REV DATE 07/08/19
DRAWING NUMBER 4C15D-17CS	DRAWN BY RAK